

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21828-00-00
Spot: NENWNE Sec/Twnshp/Rge: 23-18S-8W
4978 feet from S Section Line, 1763 feet from E Section Line
Lease Name: WILLMS Well #: 2
County: RICE Total Vertical Depth: 3650 feet

Operator License No.: 8653
Op Name: PETROLEUM TECHNOLOGIES, INC.
Address: 801 W 47TH ST STE 412
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	259		210 SX
PROD	5.5	3500		175 SXS CMT

Well Type: SWD UIC Docket No: D23442.0 Date/Time to Plug: 04/08/2010 10:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2010 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND BOTTOM TO 3300' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1100', 750', AND 310'. RUN TUBING TO 1100' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CALCIUM. PULL TUBING TO 750' AND PUMP 35 SX'S COMMON CEMENT WITH CALCIUM. PULL TUBING TO 310' AND CIRCULATE 60-40 POZ 4% GEL TO SURFACE. SHUT VALVE ON 5.5" AND CIRCULATE CEMENT UP BACKSIDE OF 5.5". PULL TUBING OUT AND TOP OFF. USED 190 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3500	3650	OH	

INVOICED
DATE 4/29/10
INV. NO 2010010245

Remarks: LOG TECH OF KS #6030. COPELAND TICKET C-36666

Plugged through: TBG

District: 02

Signed

Virgil Clothier

RECEIVED
KANSAS CORPORATION COMMISSION

APR 20 2010 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

JK