

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20997-00-00
Spot: NESW Sec/Twnshp/Rge: 18-34S-18W
1780 feet from S Section Line, 1980 feet from W Section Line
Lease Name: HOFFMAN TRUST B Well #: 1
County: COMANCHE Total Vertical Depth: 5625 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	684		WITH 350 SX CMT
PROD	4.5	5525	3200	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/02/2010 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 793-2316

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 04/02/2010 8:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND BACK TO 5350' & 5 SX CMT. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5406	5416		

INVOICED
DATE 4/29/10
INV. NO. 2010010246

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
APR - 5 2010
KCC DODGE CITY

RECEIVED
APR 12 2010
KCC WICHITA

Form CP-2/3