

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23337-00-00
Spot: NWNE Sec/Twnshp/Rge: 4-30S-15W
560 feet from N Section Line, 2150 feet from E Section Line
Lease Name: LEE "F" Well #: 2
County: BARBER Total Vertical Depth: 4850 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		WITH 450 SX CMT
PROD	5.5	4724	2480	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2010 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200 # HULLS & 25 SX CMT. PLUG AT 1000' WITH 20 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2010 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP DOWN 5 1/2" CASING WITH 200# HULLS & 25 SX CMT. TAG CMT PLUG AT 4400'. 1ST PLUG AT 1000' WITH 20 SX GEL & 50 SX CMT W/50# HULLS. 2ND PLUG AT 600' WITH 50 SX CMT W/50# HULLS. 3RD PLUG AT 50 SX CMT W/50# HULLS. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4610	4614		VIOLA

INVOICED
DATE 4/29/10
INV. NO. 2010010246

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
APR 13 2010
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

APR 26 2010

CONSERVATION DIVISION
WICHITA, KS

Form CD 2/3