

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25404-00-00  
Spot: SESENENW Sec/Twnshp/Rge: 4-20S-11W  
1160 feet from N Section Line, 2334 feet from W Section Line  
Lease Name: KUMMER Well #: 4-4  
County: BARTON Total Vertical Depth: 3420 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/28/2010 12:00 PM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: GARY KUMMER Company: RAMA OPERATING CO., INC. Phone: (620) 234-5191

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE  
Date/Time Plugging Completed: 03/28/2010 12:30 PM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 3214' w/25 sxs.  
2nd. Plug at 510' w/25 sxs.  
3rd. Plug at 340' w/80 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

Remarks: BASIC CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 

(TECH) RECEIVED cm

APR 12 2010

Form CP-2/3

KCC WICHITA

APR 07 2010