

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25035-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 10-19S-21W
370 feet from N Section Line, 1070 feet from E Section Line
Lease Name: STIEBEN Well #: 2-10
County: NESS Total Vertical Depth: 4268 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	214		WITH 150 SX CMT
PROD	5.5	4267	2973	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2010 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: SAND 50' ABOVE PERFS & 4 SX CMT. PLUG AT 1430' WITH 50 SX CMT. PLUG AT 700' WITH 80 SX CMT. PLUG AT 240' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2010 5:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 4200' & 4 SX CMT. LOST DUMP BAILER IN HOLE @ 4200'. 1ST PLUG AT 1430' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4260	4268		MISSISSIPPIAN

INVOICED
DATE 5/04/10
INV. NO. 2010010260

RECEIVED
KANSAS CORPORATION COMMISSION

APR 30 2010

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
APR 23 2010
KCC DODGE CITY

Form CP-173