

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20147-00-00
Spot: SESW Sec/Twnshp/Rge: 15-34S-21W
897 feet from S Section Line, 3256 feet from E Section Line
Lease Name: SHUPE Well #: 1-15
County: CLARK Total Vertical Depth: 5750 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5300		WITH 2 SX CMT
SURF	8.625	650		WITH 750 SX CMT
PROD	5.5	5750	1950	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/20/2010 1:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 5330' WITH 2 SX CMT. PLUG AT 830' WITH 20 SX GEL & 50 SX CMT. PLUG AT 680' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACCLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2010 2:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5300' WITH 2 SX CMT. 1ST PLUG AT 830' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 680' WITH 40 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5382	5416		

INVOICED
DATE: 5/04/10
INV. NO. 2010010264

RECEIVED
KANSAS CORPORATION COMMISSION

APR 30 2010

Remarks: USED 60/40 POZMIX 4% GEL QUALITY OILWELL CEMENTING

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

Signed

Jerry W. Stapleton
PART II (TECHNICIAN)

RECEIVED

APR 23 2010

KCC DODGE CITY

Form CP-3/3