

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20725-00-00
Spot: SWNESW Sec/Twnshp/Rge: 15-34S-21W
1687 feet from S Section Line, 3619 feet from E Section Line
Lease Name: SHUPE A Well #: 2-15
County: CLARK Total Vertical Depth: 5580 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5000		WITH 2 SX CMT
SURF	8.625	852		WITH 575 SX CMT
COND	20	85		WITH 300 SX CMT
PROD	5.5	5576	2100	WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2010 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd, from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 5000' WITH 2 SX CMT. PLUG AT 880' WITH 20 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL
Date/Time Plugging Completed: 04/21/2010 11:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG RAN TBG TO 880' & PUMP 20 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 250' & PUMP 40 SX CMT. NO RETURNS. PUMP ADDITIONAL 20 SX CMT. NO FLUID TO SURFACE. SDON. 4/21/10: TOC @ 286'. 3RD PLUG LOAD HOLE WITH GEL, BROKE CIRCULATION. TBG AT 250'. PUMP 40 SX CMT. 4TH PLUG PULL TO 60' & PUMP 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5062	5077		

INVOICED
DATE 5/04/10
INV. NO. 2010010264

RECEIVED
KANSAS CORPORATION COMMISSION
APR 30 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
APR 27 2010
KCC DODGE CITY

Signed Jerry W. Stapleton
(TECHNICIAN)
PIRT II

Form CP-23