

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21493-00-00
Spot: SESENW Sec/Twnshp/Rge: 17-15S-18W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: GRABBE Well #: 3
County: ELLIS Total Vertical Depth: 3566 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207	0	w/135 sxs cmt
PROD	5.5	3565	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2010 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: DREILING OIL, INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 800# hulls - 11 sxs gel.
Perf two holes each - 3484'-3457'; 3440'-3499'; 3549'-3551'; 3522'-3524';
3339'-3341'; 3266'-3268'; 3271'-3274'; 3288'-3294'; 3418'-3422'.
03/01/1981- Squeezed at 455' w/200 sxs.
Well was flowing - Cedar Hills break in.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2010 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

LK Wireline perfed at 1800' and 1175'.
Express Well Service RIH with tubing to 3200'.
Quality Oil Well Service rigged to tubing - pumped 11 sxs gel - followed with 75 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.
Pulled tubing to 1700'. Quality rigged to tubing - pumped 210 sxs cement with 500# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 50 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.
Rigged to 8 5/8" - pumped 10 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3565	3566	OH	


INVOICED
DATE 5/04/10
INV. NO. 2010010266

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3861.

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 30 2010

CONSERVATION DIVISION
WICHITA, KS

APR 26 2010

DREILING OIL, INC.
RR#1, VICTORIA, KS.

#3 GRABBE

17-15-18W
SE SE NW

CONTR CO. TOOLS

CTY ELLIS

GEOL

FIELD RUDER

E 2000 KB CM 5/29/78 CARD ISSUED 7/27/78 IP P 30 BOPD. N/W
ARB 3565-66

+	+
+	+

API 15-051-21,493

LOG	TOPS	DEPTH	DATUM
ANH	1154	+ 846	
TOP	2938	- 938	
HEEB	3219	-1219	
TOP	3242	-1242	
LKC	3266	-1266	
BKC	3497	-1497	
PENN CONG	3519	-1519	
ARB	3561	-1561	
TD	3566	-1566	

8-5/8" 207/135sx, 5 1/2" 3565
DST (1) 3388-3445/30-45-30-45, 120'
SOCM, 60'O&GCM, 185'H0&GCM, SIP
801-594#, FP 103-181#, 194-245#
MICT - CO TO TD, GSO NAT, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS