

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-099-20493-00-00
Spot: SWSWSWSE Sec/Twnshp/Rge: 21-34S-20E
276 feet from S Section Line, 2864 feet from W Section Line
Lease Name: LINK Well #: 1
County: LABETTE Total Vertical Depth: 423 feet

Operator License No.: 9386
Op Name: GUS JONES CABLE TOOL SERVICE, LL
Address: 149 RD 25
ELK CITY, KS 67344

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	423		

Well Type: ST UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 9386 Plug Co. Name: GUS JONES CABLE TOOL SERVICE, LLC
Proposal Rcvd. from: DONALD (GUS) JONES Company: GUS JONES CABLE TOOL SERVIC Phone: (620) 332-7637

Proposed Plugging Method: DRILLED WITH 9 INCH BIT TO 265 FT. CORED WITH 4 INCH CORE BIT TO 365 FT. REAMED WITH 9 INCH BIT TO 423 FT. SET 5 1/2 INCH CASING TO 423 FT CEMENTED WITH HIGH TEMPERATURE LUMINITE CEMENT WITH 40 PER CENT SILICA FLOUR. 1 1/2 INCH TUBING WELDED TO OUTSIDE OF CASING FOR THERMOCOUPLE. PERFORATED FROM 355 TO 367 FT WITH 2 SHOTS PER FOOT. ACID FRACTURED AT 1100 PSI. PERFORATIONS WERE SQUEEZED WITH 35 SACKS CEMENT. DRILLED OUT, PERFORATED 361-367 WITH 4 SHOTS PER FOOT. PERFORATIONS WOULDN'T TAKE FLUID. HYDROJET PERFORATED AT 362 AND 366 FT. ACIDIZED WITH 450 GALLONS 7 1/2 % HCL. ✓

Plugging Proposal Received By: RUSSELL HINE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2009 9:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran 3/4" in thermocouple plugged with 4 sacks of portland. Hooked to 5-1/2" and created rate of flow and then pumped 50 sacks of 60/40 pozmix w/ 5% gel. Shut in at 500psi.

Perfs:

INVOICED
DATE 5/04/10
INV. NO. 2010010269

RECEIVED
KCC DISTRICT #3

JUL 9 2009

CHANUTE, KS

RAH

RECEIVED
JUL 13 2009
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Russell Hine

(TECHNICIAN)