

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-099-20620-00-00  
Spot: NESWSWSE Sec/Twnshp/Rge: 21-34S-20E  
392 feet from S Section Line, 2990 feet from W Section Line  
Lease Name: LINK Well #: 4  
County: LABETTE Total Vertical Depth: 423 feet

Operator License No.: 9386

Op Name: GUS JONES CABLE TOOL SERVICE, LL

Address: 149 RD 25  
ELK CITY, KS 67344

Well Type: ST

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 9386

Plug Co. Name: GUS JONES CABLE TOOL SERVICE, LLC

Proposal Rcvd. from: DONALD (GUS) JONES

Company:

Phone: (620) 332-7637

Proposed Plugging Method: 5 1/2 INCH CASING CEMENTED WITH HIGH TEMPERATURE LUMINITE CEMENT WITH 40 PER CENT SILICA FLOUR. 1 1/2 INCH TUBING WELDED TO OUTSIDE (?) OF CASING FOR THERMOCOUPLE. PERFORATED FROM 351 TO 366 FT. WITH 6 SHOTS PER FOOT. FRACTURED WITH 3000 GALLONS PAD, 3000 GALLONS FRAC FLUID WITH 1 LB./GAL 20/40 MESH SAND, 2000 GALLONS FLUSH.

Plugging Proposal Received By: RUSSELL HINE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 05/19/2009 1:00 PM

KCC Agent: RUSSELL HINE

Actual Plugging Report:

Perfs:

Ran 3/4" in thermocouple and plugged 4 sacks. Hooked to 5-1/2" and created a rate of flow. Pumped 50 sacks of 60/40 pozmix and shut in at 400psi

RECEIVED  
KCC DISTRICT #3

JUL 9 2009

CHANUTE, KS

RHN

RECEIVED

JUL 13 2009

KCC WICHITA

INVOICED

DATE 5/04/10

INV. NO. 2010010269

Remarks:

Plugged through: CSG

District: 03

Signed

*Russell Hine*

(TECHNICIAN)