

15-055-00631-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Finney County. Sec. 7 Twp. 26 Rge. 31 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C SW
Lease Owner Nate Appleman Company
Lease Name Kisner Well No. #3
Office Address 1/2 R. W. Lange - Box 434 - Garden City, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3-1-62 19____
Plugging completed 3-3-62 19____
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2673 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 2600' with 5 sacks cement.
Mudded hole to 550' and sat 10' rock bridge with 20 sacks cement with dump baler
Mudded hole to 40' and sat 10' rock bridge with 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spenser Sec. - Treas.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of March, 1962

My commission expires 24 October 1964
Sidney D. Miller
Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- N. APPLEMAN COMPANY
Farm- Kisner No. 3


SEC. 7 T. 26 R. 31W
C SW/4
1320'N & 1320' E of SW Corner

Total Depth. 2677
Compt. 12-27-54 Comp. 1-13-55

County Finney

Shot or Treated.
Contractor. Burris Drilling Co. & Northern Pump Co.
Issued. 5-4-57

KANSAS



Elevation. 2848 KB

CASING:
8 5/8" 780; cem w/350 sx.
5 1/2" 2633' cem w/150 sx.

Production. 2,200,000 gas in
4 hour blow down

Figures indicate Bottom of Formations

NO LOG AVAILABLE.

Tops:

Base Stone Corral 1926
Hollenberg 2608-2620
Herington 2631-2652
Kridler 2655

- 1- 9-55 2661 First show of gas @ 2642
- 1-10-55 2677 Well gauged 2980,000 cu.f.
per day rate of gas.
Shut down over night.
- 1-11-55 Checked hole for salt water.
Found none.
Treated w/6000 gals. Jetra-Frac w/2# sand,
1000 gals. D. Fuel, 1000Gal. 15% 6000 gal.
1000 gals Diesel 2600 gals. 7 1/2% wash,
2600, gals. water. @ 2633-2677
Let stand 4 hrs. & started swabbing.
Pulled swab two time & broke pin on
stem while out of hole. Shut down
overnight for repairs.
- 1-12-55 Finished swabbing well. Well
started flowint @ 10 a.m.
4 hr. blow down gauge 2,200 MCF.
Let well blow over night to clean
up.