


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Sheridan County, Sec. 10 Twp. 10S Rge. 26W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NW SW SW
Lease Owner Hinkle Oil Company
Lease Name Troutman Well No. 1
Office Address 1016 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed August 25, 19 75
Application for plugging filed August 25, 19 75
Application for plugging approved August 25, 19 75
Plugging commenced August 25, 19 75
Plugging completed August 25, 19 75
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Nichols
Producing formation Depth to top Bottom Total Depth of Well 4120 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	252.80'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug @ 1200' w/70 sx. cmt. (50-50 pozmix, 6% gel)
2nd Plug @ 250' w/20 sx. cmt.
3rd Plug @ 40' w/10 sx. cmt.

RECEIVED
STATE CORPORATION COMMISSION
9-8-1975
SEP 08 1975
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SWORN to before me this 29th day of August, 19 75



D'Ann Brennan
Notary Public.

December 28, 1977

DRILLERS LOG

No. 1 Troutman

CASING RECORD:

8-5/8" @ 252.80'
w/190 Sx. Cmt.

COMPANY: Hinkle Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: August 14, 1975

COMPLETED: August 25, 1975

DESCRIPTION:

NW SW SW
10-10S-26W
Sheridan County,
Kansas

TOTAL DEPTH: 4120'

ELEVATION: 2616' K.B.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Shale	0	255	
Shale	255	1740	
Shale & Clay	1740	1950	
Redbed	1950	2247	
Anhydrite & Shale	2247	2280	
Shale & Shells	2280	2320	
Shale	2320	2791	
Shale & Lime	2791	3030	
Shale	3030	3150	
Shale & Lime	3150	3279	
Lime & Shale	3279	3394	
Shale & Lime	3394	3495	
Lime	3495	3620	
Lime & Shale	3620	3823	
Lime	3823	4120	

RECEIVED
STATE CORPORATION COMMISSION
9-8-1975
SEP 08 1975
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 29th day of August, 1975.

D'Ann Drennan
Notary Public

My Commission Expires:

December 28, 1977



MILLERS FALLS