

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Crockett Oil & Gas, Inc.
Address: 202 N. Main Sharon, Ks. 67138
Phone: (620) 348-4093 Operator License #: 30560
Type of Well: INJ. Docket #: E-27311
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Pfeifer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-151-90975-151-70082
151-00142-00-03
Lease Name: Curtis F-1 OWWO (Gereke Unit)
Well Number: 7W-01
Spot Location (OQQQ): _____ SE _____ SE _____ NE
2970 Feet from _____ North / South Section Line
353 Feet from East / West Section Line
Sec. 10 Twp. 26 S. R. 15 East West
County: Pratt
Date Well Completed: _____
Plugging Commenced: 4-18-08
Plugging Completed: 4-22-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8"	275'	None
				5-1/2"	4302'	2008'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.
Plugged off bottom with sand to 3880' and 5 sxs. cement. Cut casing loose @2008', pulled up to 1000', pumped 10 sxs. gel and 50 sxs. cement, pulled up to 300', pumped 100 sxs. cement, pulled up to 40' and circulated 75 sxs. cement to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Crockett Oil & Gas, Inc.
State of Kansas County, Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*
(Address) P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION COMMISSION


MAY 14 2008

CONSERVATION DIVISION
WICHITA, KS

SUBSCRIBED and SWORN TO before me this 12th day of May 20 08

Irene Herzberg
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202