

15-179-20978-00-00  
11-27

6 070878

API NUMBER 15- 179-20,978

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE NE, SEC. 10, T 10 S, R 26 W/E  
4950 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9482

Operator: National Petroleum Reserves  
Name & Address: 250 N. rock Rd. #340  
Wichita, Ks. 67206  
Ted Bredehoft

Lease Name Fuller Well # 1  
County Sheridan 136.50  
Well Total Depth 4200 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A xx

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Drilling License Number \_\_\_\_\_  
Address Russell, Ks.

Company to plug at: Hour: AM \_\_\_\_\_ Day: 27 Month: Nov Year: 19 90

Plugging proposal received from John Collins

(company name) Emphasis Drilling Inc. (phone) \_\_\_\_\_

were: 8 5/8 260 ft. s.p. cwc w/175 sks 60/40 poz 2% gel 3% ca cl . By Allied Cement.

K. C. well; Elv. 2605 - anhy 2274 ft. No circ problems. Mud condition - 49 vis -  
8.8 weight. 10 water loss. Proposal 190 sks 60/40 poz 6% gel 3% ca cl. Spot with drill stem  
circ; Displace heavy mud between all plugs. 25 sks at 2280; 100 sks w/ 1 sk fc at  
1320 ; 40 sks at 300 ; 10 sks at 40; 15 sks in rathole. Circulate.

Plugging Proposal Received by *MJS* Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None xx

Operations Completed: Hour: 9:00 AM Day: 27 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Emphasis ordered 190 sks 60/40 poz 6% gel 3% ca cl circulated  
hole. Spotted with drill stem, heavy mud between all plugs.

- 1st plug at 2280 w/25 sks cement
- 2nd plug at 1320 w/100 sks cement w/ 1 sk f.c.
- 3rd plug at 300 w/40 sks cement
- 4th plug at 40 w/10 sks cement

RECEIVED  
STATE CO. 15 sks in rathole circulate by Hall-  
iburton.  
DEC 10 1990  
12-10-1990  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed *Marion J. Schmidt*  
(TECHNICIAN)  
Marion J. Schmidt

DATE 12-14-90  
TV. NO. 30262