

To: 6 031514
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-20
15-179-20978-00-01
API NUMBER 15- 179-20,978 A

NE NE NE, SEC. 10, T 10 S, R 26 W/E
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30075
Operator: Shamrock Resources Inc.
Name & Address: 100 N. Main #802
One Main Place bldg.
Wichita, Ks. 67202

Lease Name Ruller Well # 1
County Sheridan 134.12
Well Total Depth 4127 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: PM Day: 20 Month: Mar Year: 19 91

Plugging proposal received from Manny
(company name) Kelso (phone)

were: 8 5/8 set at 260 w/175 sks cwc. 4 1/2 set at 4123 w/145 sks. Perf 3892-4068

Order sand and common cement. Pull pipe, order 225 sks 65/35 poz 10% gel
500 lbs. hulls. Allied Cement Co. Walker water trucks.

Ran bailer to 2100. Hole open.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 20 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 3840 w/4 sks common cement on sand
w/bailer. Recovered 2000 casing. Sq 8 5/8 w/225 sks cement blend w/500 lbs.
hulls mixed in to max psi 400 lbs. Close in psi 200 lbs.

RECEIVED
STATE CORPORATION COMMISSION

APR 04 1991
4-4-1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED
DATE 4-11-91
INV. NO. 31501

J.L.S.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow