

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-22180-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 11-31S-34W
2100 feet from N Section Line, 1100 feet from E Section Line
Lease Name: IVES Well #: 11 #1
County: SEWARD Total Vertical Depth: 5900 feet

\$191.75

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 1702 | | WITH 500 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/29/2010 2:30 PM
Plug Co. License No.: 34000 Plug Co. Name: KENAI MID-CONTINENT, INC.
Proposal Rcvd. from: MIKE KNOX Company: EOG RESOURCES Phone: (405) 246-3100

Proposed Plugging Method: 1ST PLUG AT 1730' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 04/29/2010 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1730' WITH 100 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

Plugged through: DP

District: 01

Signed Eric MacLaren
RECEIVED
KANSAS CORPORATION COMMISSION
(TECHNICIAN)

RECEIVED
MAY - 7 2010
KCC DODGE CITY

MAY 12 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE: 5/13/10
INV. NO. 2010061090

Form CP-20