

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23384-00-00
Spot: SWNWESW Sec/Twnshp/Rge: 30-29S-8E
2209 feet from S Section Line, 8858 feet from E Section Line
Lease Name: KENT Well #: 2
County: BUTLER Total Vertical Depth: 2900 feet

\$ 94.25

Operator License No.: 5242
Op Name: PETROLEUM MANAGEMENT, INC.
Address: 14201 E CENTRAL
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2790		
SURF	8.625	210		115 SX
PROD	5.5	2897	1000	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2010 8:00 AM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Rcvd. from: GARY REED Company: PETROLEUM MANAGEMENT INC Phone: (316) 655-8775

Proposed Plugging Method: AS PER KCC RULES & REGS, SPOT 10 SXS CEMENT ON TOP OF THE CIBP, SQUEEZE HOLES @ 260, CIRCULATE CEMENT FROM 260'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/08/2010 10:15 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

QUALITY WELL SERVICE CIRCULATED HOLE CLEAN @ 2790 AND TAGGED CIBP. W/TBG @ 2780', QUALITY WELL SERVICE MIXED & PUMPED 10 SXS 60/40 POZMIX 4% GEL AND DISPLACED IN CASING. CUT CASING @ 1160', LAYED DOWN 29 JTS 5-1/2" CASING. 4-8-2010, RIH W/TBG @ 262', COPELAND ACID SERVICE MIXED & PUMPED 82 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET 334605. 4-12-2010 TAGGED TOP PLUG @ 75'. 4-13-2010, TOPPED WELL OFF, COPELAND ACID SERVICE MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. PLUG DOWN 12:40 PM, 4-13-2010. CEMENT TICKET #34607.

Perfs:

Top	Bot	Thru	Comments
2831	2834	CSG	

INVOICED
DATE: 5/13/10
INV. NO. 2010061092

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 05 2010

Remarks:

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
(TECHNICIAN)

154