

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20770-00-00
Spot: SESWSW Sec/Twnshp/Rge: 10-9S-27W
613 feet from S Section Line, 4613 feet from E Section Line
Lease Name: WHITE Well #: 1
County: SHERIDAN Total Vertical Depth: 4145 feet

#134.71

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256	0	w/200 sxs cmt
PROD	5.5	4146	0	w/175 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2010 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: LEON PFEIFER Company: RL INVESTMENT, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered 450 sxs cement and 500# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2010 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 256' w/200 sxs cement.
5 1/2" production casing set at 4146' w/175 sxs cement.
Perforated at 2280' w/350 sxs cement.
TD 4145'. PBSD 4097'.
Ran tubing to 2500' - pumped 280 sxs cement with 400# hulls.
Pulled tubing to 1200' - pumped 85 sxs cement - cement to surface.
Pulled tubing to surface. Topped production casing with 25 sxs cement.
Connected to 8 5/8" surface casing - pumped 35 sxs cement.
Max. P.S.I. 300#.

Perfs:

Top	Bot	Thru	Comments
3885	3888		
3840	3844		

INVOICED
DATE 5/13/10
INV. NO. 2010061094

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 05 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: S.O.S. CEMENTING COMPANY-TICKET #435.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

SHARON RESOURCES, INC.
 7100 E. BELLEVIEW ST., #201
 ENGLEWOOD, CO 80111

#1 WHITE

10-9-27W
 590' FSL &
 700' FWL SW/4

CONTR MURFIN DRILLING COMPANY CTY SHERIDAN

GEOL ROBERT ELDER FIELD WC(1/2 S OF MCFADDEN, SEP BY DRY HOLES)

ELEV 2706 KB SPD 11/11/84 CARD ISSUED 7/4/85 IP P 17 BO & 110 BWPD
 2701 GL DRLG COMP 11/17/84 SHAW(TOR) 3840-3844
 LKC 3885-3888



SMP	Tops	Depth Datum
ANH	2295+ 411
TOP	3584- 878
HEEB	3819-1113
TOR	3841-1135
LANS	3860-1154
BKC	4099-1353
PBTD	4097-1351
RTD	4145-1439

API 15-179-20,770
 8 5/8 " 256 / 200SX, 5 1/2 " 4146 / 175SX
 NO CORES
 DST (1) 3873-3920 (LKC B) / 30-45-45-60, REC 150' CL SLT GSY OIL, 150' HMCO (65% OIL, 35% M), 110' HMCO (45% OIL, 10% W, 45% M), SIP 1056-1046#, FP 39-108 / 118-157#, HP 1886-1881#
 DST (2) 3916-52 (LKC G) / 30-45-45-60, REC 1120' SW, SIP 1175-1175#, FP 39-285 / 290-511#, HP 1930-1915#
 MICT - CO, PF (LKC) 3885-88, W / 2 SPF, AC 250G (15% MA), SWB LD, SO, PF (TOR) 3840-44, W / 4 SPF, AC 1500G (15% DEMEL), SWB LD, SO, SET 2 7/8 " TBG AT 3922', POP, P 17 BO & 110 BWPD, COMMINGLED, 2/7/85

NOTE: CORRECTION, 5/16/85 - ORIGINALLY FIRST REPORTED IN C SW SW

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC
 WICHITA, KANSAS