

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-03032-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 33-15S-11W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: DAVIDSON Well #: 3  
County: RUSSELL Total Vertical Depth: 3289 feet

\$ 106.89

Operator License No.: 6883  
Op Name: ROBINOWITZ OIL COMPANY, A GENE  
Address: 4200 E SKELLY DR STE 620  
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	309	0	175 SX
PROD	5.5	3288	0	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/03/2010 2:30 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DICKSON Company: ROBINOWITZ OIL COMPANY Phone: (620) 786-4258

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel.  
Sanded bottom - topped with 5 sxs cement to pull casing - could not pull casing.  
Decided to run tubing to plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/03/2010 7:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 700' - 290'.  
Ran tubing to 3000' - pumped 12 sxs gel - followed with 35 sxs cement with 150# hulls.  
Pulled tubing to 1600' - pumped 85 sxs cement with 150# hulls.  
Pulled tubing to 750' - circulated to surface with 110 sxs cement with 100# hulls.  
Pulled tubing - tied to casing - pumped 50 sxs cement - circulated out surface pipe.

Perfs:

Top	Bot	Thru	Comments
3288	3289		ARBUCKLE

5/13/10  
2010061096

Remarks: COPELAND ACID AND CEMENTING-TICKET #36516.

Plugged through: CSG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

RECEIVED

MAY 10 2010

KCC WICHITA

Form CP-2/3

MAY 05 2010

ROBINOWITZ OIL

#3 DAVIDSON

33-15-11W  
NW SW SW

Contr. SHOLOM DRILLING

RUSSELL County

E 1819KB Comm. 3/9/63 Comp. 5/9/63 IP PMP 100 BOPD, NW/  
ARB 3284 $\frac{1}{2}$ -89

SMP Tops	Depth	Datum
TOP	2607	-788
PLATTSMOUTH	2792	-973
HEEB	2851	-1032
TOR	2867	-1048
DOUG	2882	-1073
LANS	2942	-1123
B/KC	3195	-1376
CONG	3242	-1423
ARB	3283	-1464
TD	3289	-1470

**Casing**  
 8" 309/175 SX:  
 5" 3284 $\frac{1}{2}$ /100 SX:  
 DST 2784-2840/2 HRS, 135' MW, BHP  
 1060-950#/30", FP 100-180#:  
 DST 2858-2961/2 HRS, 135' MW, SLI  
 GC, IBHP 1000#, NO RFBHP, FP  
 125-175#:  
 DST 2956-3145/2 HRS, 480' MW, BHP  
 1000#/20"-840#/30", FP 200-200#:  
 DST 3234-89/2 HRS, WB, 60' OCM,  
 60' HOCM, 180' V HOCM, 600' MO,  
 BHP 1000#/20"-985#/30", FP 140-  
 500#:  
 NO LOG:

DAVIDSON

+	+	+
+	+	+
+	+	+

COTD: FU 650' OIL/1 HR  
FU. 2200' OIL/12 HRS,  
NATL: POP:

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS