

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20890-00-00
Spot: SWNESE Sec/Twnshp/Rge: 36-12S-34W
2270 feet from S Section Line, 620 feet from E Section Line
Lease Name: BRIAN BECKMAN Well #: 1-36
County: LOGAN Total Vertical Depth: 4750 feet

#154.38

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 1469
PLAINFIELD, IL 60544

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/25/2010 9:00 PM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: JAMES SCHULTZ Company: RUSSELL OIL, INC. Phone: (815) 609-7000

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Drill pipe got stuck in the hole at 1050' - 1510' while straddle testing at 4255' - 4336'.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 04/25/2010 10:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug perfed at 2555' w/25 sxs.
2nd. Plug perfed at 1428' w/100 sxs.
3rd. Plug perfed at 960' w/25 sxs. Backed off drill pipe at 926'.
4th. Plug at 350' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

5/13/10
2010061097

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed CASE MORRIS
(TECHNICIAN)

RECEIVED

MAY 10 2010

KCC WICHITA

MAY 03 2010