

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25972-00-00 \$ 117.5
Spot: SWNESWNE Sec/Twnshp/Rge: 34-15S-17W
1690 feet from N Section Line, 1780 feet from E Section Line
Lease Name: JACOBS Well #: 1-34
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1064		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/06/2010 1:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: FRANK Company: SAMUEL GARY JR. & ASSOCIATES Phone: (303) 831-4673

Proposed Plugging Method: Ordered 160 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 05/06/2010 2:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 1115' w/25 sxs.
2nd. Plug at 400' w/80 sxs.
3rd. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

RECEIVED

MAY 10 2010

KCC WICHITA

Form CP-2/3

MAY 06 2010