

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24442-00-00
Spot: NENWSW Sec/Twnshp/Rge: 19-20S-15W \$ 127.56
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: IANNITTI Well #: 5
County: BARTON Total Vertical Depth: 3925 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1135	0	400 SX
PROD	5.5	3924	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/28/2010 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (620) 793-5838

Proposed: Ordered 200 sxs 60/40 pozmix - 4% gel - 200# hulls - 17 sxs gel.
Plugging: Tried to pull casing - shot off casing at 1649' and 1569' - would not come loose.
Method: Decided to run tubing to plug.
Perfed at 1080' and 700'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/28/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3600' - tied to tubing and pumped 17 sxs gel - followed with 25 sxs cement with 50# hulls.
Pulled to 1700' - pumped 125 sxs cement with 200# hulls.
Pulled to 850' - pumped 50 sxs cement - circulated cement to surface.
Pulled tubing - topped with 10 sxs cement.
Max. P.S.I. 300#.
Tied to surface - pipe would not take cement.
Max. P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
3851	3853		
3838	3841		
3830	3832		
3821	3823		
3815	3818		

5/13/10
201006100

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

RECEIVED

MAY 10 2010

KCC WICHITA

Form CP-2/3

MAY 03 2010

STATE: KANSAS COUNTY: BARTON 19-20S-15W
FIELD: PAWNEE ROCK 1/4 MI SW PROD(ARBUCKLE) NE NW SW
OPER: IANNITTI OIL 2310 FSL 4290 FEL SEC
WELL: 5 IANNITTI WELL CLASS: WOE ELEV: 2115 KB
API: 15-009-24442 STATUS: OIL 2110 GR
SPUD: 02/20/91 COMP: 03/08/91
DTD: 3925 LTD: FTD: ARBUCKLE PBTD: 3913

LOC: 3 MI NW PAWNEE ROCK, KS

IP: COMP 3/8/91, IPP 50 BO, 5 BWPD, GTY 38 PROD ZONE- ARBUCKLE 3815-3823
GROSS
NO CORES, THREE DSTS (ARBUCKLE EXTENSION)

LOG TOPS:

ANHYDRITE	1120 995	BROWN LIME	3515 -1400
BSE ANHYDRITE	1147 968	LANSING	3530 -1415
HEEBNER	3426 -1311	BSE KANSAS CITY	3752 -1637
TORONTO	3445 -1330	ARBUCKLE	3810 -1695
DOUGLAS	3454 -1339		
TD	3925 -1810		

LOG TYPES: CDL, DILL, ML:

CSGS: 8 5/8 @ 1135 W/400 SX, 5 1/2 @ 3924 W/150 SX; TBG: 2 7/8 @ 3896; DRLG COMP
02/26/91 RIG REL 02/26/91

(OVER)

COPYRIGHT 1991 PETROLEUM INFORMATION CORPORATION

DATE 11/08/91 CARD #00019-KS