

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20074-00-00
Spot: NWNE Sec/Twnshp/Rge: 25-4S-37W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: GIBSON Well #: 1
County: CHEYENNE Total Vertical Depth: 4969 feet

161.49

Operator License No.: 31514
Op Name: THOROUGHBRED ASSOCIATES L.L.C.
Address: 8100 E 22ND ST STE 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	365	0	w/250 sxs cmt
PROD	4.5	4932	0	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/28/2010 10:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: ROBERT PATTON Company: THOROUGHBRED ASSOCIATES L. Phone: (316) 685-1512

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 700# hulls - 12 sxs gel - 2 sxs CC.
Plug through tubing.
05/03/2010 - Ordered 100 sxs cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/28/2010 5:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 365' w/250 sxs cement.
4 1/2" production casing set at 4932' w/200 sxs cement.
TD 4969'. Casing has holes.
Perforated production casing at 2340' - 3077'.
Ran tubing to 4650' - pumped 12 sxs gel and 50 sxs cement with 300# hulls.
Pulled tubing to 3075' - pumped 110 sxs cement mixed with 2 sxs C.C. and 150# hulls.
Pulled tubing to 1550' - pumped 125 sxs cement with 150# hulls - cement to surface.
Pulled tubing to surface. Topped production casing with 35 sxs cement.
8 5/8" to be cemented later.
05/03/2010 - Connected to 8 5/8" surface casing - pumped 70 sxs cement.

Perfs:

Top	Bot	Thru	Comments
4675	4680		
4659	4669		

5/13/10
2010061101

Remarks: ALLIED CEMENTING COMPANY-TICKET #43611 & #39288.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

CM

RECEIVED

MAY 10 2010

KCC WICHITA

Form CP-2/3

MAY 03 2010

REPLACEMENT CARD


WYOMING PETROLEUM CORPORATION
 P.O. BOX 17485
 SAINT ANTONIO, TX 78217
 #1 GIBSON
 25-4-37W
 C. NW NE

OWNER RAVINS & WILLIAMSON CITY CHEYENNE

GEOLOGICAL FIELD WC (LITTLE BEAVER CREEK NO. DISC)

WELL 33240 KB SPD 7/14/78 CARD ISSUED 10/5/78 P. P. 322 BOPD
 (CHER 4659-4660) OA

API 15-023-20,074



LOG	Top	Depth/Perm.
NJOB		1120-2220
SC		3032-278
LANS		4202-862
MAYRM		4456-1126
CHER		4666-1296
MISS		4848-1508
RTD		4969-1629

8 5/8 " 965 / 250SX, 4 1/2 " 4982 / 200SX
 DST (0) FORM & INTV NA / MISRUN
 DST (2) 4575-1615 (MARM) / 30-30-0-0, REC 10' M, ISIP 691#
 HP 41-44# / HP 2369-2367#
 DST (3) 4698-4969 (CHER, MISS) / 15-30-15-30, REC 2:00
 MGSW, SIP 1221-1222# / HP 1013-1157 / 1115-1220# / HP
 2659-2613#
 DST (4) 4664-4969 (CHER, MISS) / 15-15-0-0, REC 300' WH600,
 1600' VHG & HOGM, ISIP 1594# / HP 1101-1206# / HP 2577-
 2541#
 MGT - CO, PF (CHER) 4659-4669 & 4675-4680, SO, NAT, POP,
 P. 322 BOPD, NW

INFO RELEASED: 6/29/86 - CORRECTED FIELD NAME
 NOTE: INFO RELEASED: 6/23/79 - RELEASED TOPS & DST'S

COPYRIGHTS
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS