

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20403-00-00

\$112.48

Spot: NWNENE

Sec/Twnshp/Rge: 23-22S-2W

4944 feet from S Section Line,

989 feet from E Section Line

Lease Name: SPERLING

Well #: 1

County: HARVEY

Total Vertical Depth: 3461 feet

Operator License No.: 5399

Op Name: AMERICAN ENERGIES CORPORATION

Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213		150sx
PROD	5.5	3460	439	175sx

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 04/29/2010 1:30 PM

Plug Co. License No.: 5399

Plug Co. Name: AMERICAN ENERGIES CORPORATION

Proposal Rcvd. from: DOUG WARD

Company:

Phone: (620) 654-7149

Proposed Plugging Method:

AS PER KCC

Plugging Proposal Received By:

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/29/2010 2:30 PM

KCC Agent: SHANE JONES

Actual Plugging Report:

4/29/2010 AMERICAN ENERGIES MOVED IN AND RAN TOOLS TO BOTTOM. THEY THEN DROPPED SAND AND LET IT FALL. AFTER LUNCH THEY WENT IN AND TAGGED SAND @ 3201' AND CAPPED IT W/5SX. THEY RIPPED CASING AT 439'. THEY THEN PULLED 1 JOINT APPROX 28'. COPELAND TIED ON AND CIRCULATED CEMENT TO SURFACE. AMERICAN ENERGIES PULLED CASING. THE HOLE STILL STANDING FULL OF CEMENT. THEY CLEANED UP AND RIGGED DOWN. THEY FINISHED @ 2:30 PM USING 225SX OF 60/40 POS W/4% GEL. TK #34619

Perfs:

Top	Bot	Thru	Comments
3426	3432	CSG	SIMPSON
3262	3266	CSG	HUNTON

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 05 2010


Remarks:

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed



(TECHNICIAN)

14