

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21048-00-00 \$ 100.00
Spot: W2NE Sec/Twnshp/Rge: 1-34S-1E
3960 feet from S Section Line, 1980 feet from E Section Line
Lease Name: GRESSEL Well #: 1
County: SUMNER Total Vertical Depth: 3077 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		175 SX
PROD	4.5	3080	1310	110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50 FT ABOVE THE PERFS AND CAP WITH 4 SKS OF CMT. RECOVER CASING. RUN TUBING TO 350' AND CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 04/06/2010 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED FROM 3077' TO 2960' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 1310' AND PULLED FROM THE WELLBORE. TUBING WAS RUN TO 325', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3016	3022	CSG	

Remarks: COPELAND CEMENTING 34600 60/40 4% GEL

Plugged through: TBG

District: 02

Signed _____


(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 10 2010

CONSERVATION DIVISION
WICHITA, KS

SK