

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21100-00-00 \$ 98,54
Spot: E2NWNE Sec/Twnshp/Rge: 1-34S-1E
4620 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GRESSEL Well #: 2
County: SUMNER Total Vertical Depth: 3032 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		175 SX
PROD	4.5	3024	1350	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK THE PERFS, 50' AND CAP WITH 4 SKS OF CMT. RECOVER CASING. CIRC CMT FROM 350-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 04/07/2010 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND FROM 3024'-2965', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 1350', AND PULLED FROM THE WELL BORE. TUBING WAS RUN TO 350', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3024	3032	CSG	

Remarks: COPELAND CMT AND ACID 60/40 4% #34602

Plugged through: OH

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 10 2010

CONSERVATION DIVISION
WICHITA, KS