

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-19153-00-01  
Spot: SESWNW Sec/Twnshp/Rge: 2-21S-9W  
3026 feet from S Section Line, 4428 feet from E Section Line  
Lease Name: GILLEN OWWO Well #: 3  
County: RICE Total Vertical Depth: 3683 feet

# 119.70

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3290		2 SX
SURF	8.625	200		175 SX
T1	2.375	2894		
PROD	5.5	3454		200 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2010 4:30 PM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Rcvd. from: ROBERT GRANT Company: BEREXCO INC Phone: (316) 772-8160

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/13/2010 6:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. CIBP ALREADY SET @ 2900'. DUMP 2 SX'S CEMENT ON CIBP. PERFORATE @ 1200', 750' AND 250'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 750' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE 50 SX'S CEMENT TO SURFACE. SHUT VALVE ONO PRODUCTION CASING AND CIRCULATE CEMENT OUT OF SURFACE CASING. PULL TUBING OUT AND PUMP CEMENT DOWN PROD. CASING SHUTTING IN BOTH CASINGS AT 50#S PRESSURE. CIRCULATION WAS PRESENT THRU-OUT JOB. USED 209 SX'S CEMENT. TOPPED OFF WITH APPROX 2.75 YDS. SLURRY MIX ON 4-20-2010, MID AMERICA TICKET #51837.

Perfs:

Top	Bot	Thru	Comments
3342	3358	CSG	SIMPSON
2938	2944	CSG	LKC 'B'
2900		CSG	LOCKSET

*Virgil Clothier*  
5/10/10  
2010061070

Remarks: 60-40 POZ, 4% GEL. PERF TECH TICKET #7231. ALLIED CEMENT TICKET #036408

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 10 2010

CONSERVATION DIVISION  
WICHITA, KS

*1/2*