

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19495-00-00 \$ 88.00
Spot: SWSWNE Sec/Twnshp/Rge: 23-28S-7E
2950 feet from S Section Line, 2348 feet from E Section Line
Lease Name: BREWER Well #: 2
County: BUTLER Total Vertical Depth: 2725 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020 AZTEC OIL CO.
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD 7		2712		35 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2010 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: STEVEN W KILE Company: AZTEC OIL CO Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/14/2010 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2661', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL 3% CC. AND DISPLACED IN CASING. WAITED 2 HOURS. TAGGED CEMENT @ 2509'. PRESSURED CASING, HELD OK. SHOT SQUEEZE HOLES @ 250', RIH W/TBG @ 250', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, & MIXED & PUMPED 180 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TBG. SWEDGED INTO 7" CASING FINISHED PUMPING 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1:00 PM, 4-14-2010. 280 SXS TOTAL FOR TOP PLUG. CEMENT TICKET #24124.

Perfs:

Top	Bot	Thru	Comments
2712	2725	OH	OH

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 05 2010


CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)