

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19496-00-00 \$ 89.18
Spot: SWNENWSE Sec/Twnshp/Rge: 23-28S-7E
2094 feet from S Section Line, 1711 feet from E Section Line
Lease Name: BREWER Well #: 4
County: BUTLER Total Vertical Depth: 2744 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020 AZTEC OIL Co.
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD 7		2726		40 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2010 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: STEVEN W KILE Company: AZTEC OPIL CO Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/08/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

PARTED TBG & OUTSIDE CASING @ 1550'. RIH W/TBG @ 1550', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 3% CC. AND DISPLACED IN CASING. WAITED 2 HOURS. TAGGED CEMENT @ 1492'. PRESSURED CASING, HELD OK. SHOT SQUEEZE HOLES @ 254', SWEDGED INTO 7" CASING, CONSOLIDATED OIL WELL SERVICES POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE. 5:00 PM, 4-8-2010. CEMENT TICKET #23366.

Perfs:

Top	Bot	Thru	Comments
2726	2744	OH	OH

Handwritten: 5/10/10
2010061071

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 05 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: PARTED TBG @ 1550'

Plugged through: TBG

District: 02

Signed _____

Handwritten Signature: Duane Krueger

(TECHNICIAN)

Handwritten: ✓JK