

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22652-00-00 \$130.5
Spot: SWNWSE Sec/Twnshp/Rge: 32-12S-21W
1850 feet from S Section Line, 2250 feet from E Section Line
Lease Name: EDWARD Well #: 1-32
County: TREGO Total Vertical Depth: 4000 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/12/2010 7:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOJ ALM Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 621-2610

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 04/12/2010 7:45 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3900' w/25 sxs.
2nd. Plug at 1680' w/25 sxs.
3rd. Plug at 900' w/100 sxs.
4th. Plug at 270' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED

MAY 10 2010

KCC WICHITA

MAY 03 2010