

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22102-00-00 \$119.11
Spot: NENWNW Sec/Twnshp/Rge: 20-22S-11W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: AIKEN NORTH Well #: 1
County: STAFFORD Total Vertical Depth: 3665 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	289		WITH 250 SX CMT
PROD	5.5	3661	632	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2010 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3250' & 5 SX CMT. PLUG AT 660' WITH 7 SX GEL & 50 SX CMT. PLUG AT 330' WITH 65 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2010 10:25 AM KCC Agent: RICHARD LACEY

Actual Plugging Report: SANDED TO 3530' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 660' WITH 7 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 65 SX CMT. 3RD PLUG AT 60' WITH 35 SX CMT. GOOD CIRCULATION THROUGH OUT JOB.

Perfs:
5/10/10
2010061074

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.
Plugged through: CSG

District: 01

RECEIVED
APR 22 2010
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form GE 213

MAY 05 2010