

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-193-20,279-0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR FIRST ENERGY CORPORATION OPERATORS LICENSE NO. 07506

ADDRESS 16701 GREENSPPOINT PARK DRIVE, HOUSTON, TX 77060 PHONE # (713) 875-5755

LEASE (FARM) SUMMERS 68-25 WELL NO. 1 WELL LOCATION C-SE-SW-SE COUNTY THOMAS

SEC. 25 TWP. 10S RGE. 31 (E) or (W) TOTAL DEPTH 4610 PLUG BACK TD 4185

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8 SET AT 319 CEMENTED WITH 225 SACKS

CASING SIZE 4-1/2 SET AT 4609 CEMENTED WITH 100sx lite  
225 sx comm SACKS

PERFORATED AT Lansing "H" Zone 4,116-22' 2SPF

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Mix & pump 20 sx B.J. lite cement, follow  
w/400# cotton seed hulls in lite cement slurry and then follow w/+ 200 sx B.J. lite and displace  
hulls and cement to perforations leaving cement + 6' below GL, cut casing off and weld on cap.  
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN August 31, 1990

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Earl Evers PHONE # (316) 564-3516

ADDRESS P.O. BOX 71, Ellinwood, KS. 67526

PLUGGING CONTRACTOR POE Servicing Inc LICENSE NO. 3152

ADDRESS P.O. Box 115, Oberlin, KS: 67749-0115 PHONE # (913) 475-3422

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Christine Harris  
(Operator or Agent)

DATE: 8/22/90

(4)

AUG 23 1990  
8-23-90  
CONSERVATION DIVISION  
Wichita, Kansas

6/90

10/90



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
 KEITH R. HENLEY CHAIRMAN  
 RICH KOWALEWSKI COMMISSIONER  
 JACK SHRIVER COMMISSIONER  
 JUDITH MCCONNELL EXECUTIVE DIRECTOR  
 FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
 SHARI FEIST ALBRECHT, DIRECTOR  
 200 Colorado Derby Bldg.  
 202 W. 1st Street  
 Wichita, KS 67202-1286  
 (316) 263-3238

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION**

August 23, 1990

First Energy Corp.  
 16701 Greenspoint Park Dr.  
 Houston, TX 77060

Summers 68-25 #1  
 C SE SW SE 25-10-31W  
 Thomas County, KS  
 API No. 15-193-20,279 -0000

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

*David P. Williams*

David P. Williams  
 Production Supervisor

District: #4, 2301 E. 13th  
 Hays, KS 67601  
 (913) 628 - 1200