

15-193-00040-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 119-4

LOCATION SE SE SE

SEC. 1 TWP. 10 RGE. 51

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Ostmeyer \_\_\_\_\_

Operator Natl Associated Pet Address Ritz Bldg, Tulsa, Okla.

Field \_\_\_\_\_ County Thomas

Total Depth 4909 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 290' circulated with cement - 5 1/2" at 4340' with  
300 sax cement behind - Perforations to 4180' squeezed with cement -  
Lane Wells plugs to 4180' - Top Perforations at 3782' - Set  
plugs at 3650', rock bridge and 5 sax cement run with dump bailer,  
pulled 2708' 5 1/2", filled hole with mud to 290', set rock and  
20 sax cement, filled with mud to 30', set rock and filled hole  
to bottom cellar with cement.

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 16 1951  
CONSERVATION DIVISION  
Wichita, Kansas

*John P. Lee*  
District Conservation Agent

Date 11-13-51

**PLUGGING**  
FILE SEC-1-T-10-R-3W  
BOOK PAGE-119-LINE-14