

15-193-20009-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tilco, et al,

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name Ostmeyer Well No. 1

Location CSW-SE Sec. 1 Twp. 10 Rge. (E) (W) 31

County Thomas Total Depth 4265'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No. _____

Operation Completed: Hour 2:00 PM Day 8 Month 12 Year 1968

The Above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1700'.

Circulated hole with heavy mud. Pull DP to 1850' and displaced 100 Sx. cement thru
DP from 1850' to 1525'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/11/68

INV. NO. 8999-u

Signed: M. G. Nichols
Well Plugging Supervisor