

15-063-20094-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
12-06-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Herndon Drilling Company,

Complete Address Box #489, Tulsa, Oklahoma.

Lease Name Boone Well No. 1

Location SW-SW-SE Sec. 4 Twp. 12 Rge. (E) (W) 26

County Gove Total Depth 4200'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A I

Other well as hereafter indicated       

Plugging Contractor John O. Farmer, Incorporated,

Address Box #352, Russell, Kansas. License No.       

Operation Completed: Hour 5:15 PM Day 29 Month 11 Year 1971

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 110 Cu. Ft. cement  
thru DP from 1100' to 875'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Pichak  
Well Plugging Supervisor

12/6/71  
4771-W