

15-063-20115-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1972
04-15-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Hinkle Oil Company,
Complete Address 1016 Union Center, Wichita, Kansas.
Lease Name Walz Well No. 1
Location SE-SE-NE Sec. 34 Twp. 12 Rge. (E) (W) 26
County Gove Total Depth 3863'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Red Tiger Drilling Company,
Address 1720 Wichita Plaza, Wichita, Kansas. License No.
Operation Completed: Hour 12:00 M Day 16 Month 4 Year 1972

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 110 Cu. Ft. cement
thru DP from 1150' to 825'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. D. J. J. J.
Well Plugging Supervisor

DATE 4/18/72
INV. NO. 5584-W