

15-063-20136-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
09-28-1972
SEP 28 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc., & Petroleum Resources,

Complete Address P. O. Box #18407, Wichita, Kansas.

Lease Name Zimmerman Well No. C-1

Location NW-NE-NW Sec. 34 Twp. 12 Rge. (E) (W) 27

County Gove Total Depth 4550'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Dunne-Gardner Petroleum, Inc.,

Address Suite 250, 200 West Douglas, Wichita, Kansas. License No. _____

Operation Completed: Hour 11:15 AM Day 26 Month 9 Year 1972

The above well was plugged as follows:

352'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 110 Cu. Ft. cement
thru DP from 1200' to 875'. Pulled DP to 370' and displaced 30 Cu. Ft. cement thru
DP from 370' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. DeChok
Well Plugging Supervisor

DATE 9/28/72
INV. NO. 6382-4