

15-063-20137-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-16-1972
OCT 16 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc. & Petroleum Resources,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Roberts Well No. 1

Location NW-SW-NE Sec. 25 Twp. 12 Rge. (E) (W)28

County Gove Total Depth 4414' ~~2314'~~

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dunne-Gardner Petroleum, Incorporated,

Address Suite 250, Garvey Building, Wichita, Kans. License No.

Operation Completed: Hour 8:45 PM Day 10 Month 10 Year 1972

The above well was plugged as follows:

325'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pull DP to 1050' and displaced 110 Cu. Ft. cement
thru DP from 1050' to 725'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru
DP from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 10/17/72
INV. NO. 6482-W