

15-063-20104-00-00

OP

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
CORPORATION COMMISSION  
JAN 13 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
01-13-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Hood Well No. A-1 56.19

Location CNE-SW Sec. 9 Twp. 12 Rge. (E) (W) 30

County Gove Total Depth 4495'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 3:00 PM Day 11 Month 1 Year 1972

The above well was plugged as follows:

525'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 110 Cu. Ft. cement  
thru DP from 1375' to 1050'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 1-13-72  
5002-W