

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

01270-00-01

Lease Operator: Dart Cherokee Basin Operating Co. LLC
Address: 211 W Myrtle, Independence, Ks. 67301
Phone: (620) 331-7870 Operator License #: 33074
Type of Well: SWD Docket #: D-20,408
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5/22/2006 (Date)
by: Alan Dunning (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Weiser Depth to Top: 683 Bottom: 692 T.D. 1085
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-125-9154-0-00
Lease Name: Russell
Well Number: # 2 SWD
Spot Location (QQQQ): _____ - NW - NW - SW
2440 Feet from North / South Section Line
5080 Feet from East / West Section Line
Sec. 35 Twp. 34 S. R. 14 East West
County: Montgomery
Date Well Completed: N/A
Plugging Commenced: 5/23/2006
Plugging Completed: 5/23/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	286'	7"	0	0
		0	1085	2 7/8"	0	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1 inch pipe inside casing to 700 feet, hit hard. Ran 1 inch pipe between casing and surface pipe to 400 feet. Filled well from bottom to top with cement. Pulled out 1 inch pipe and topped off well. A total of 133 sacks of Portland cement were used to plug this well.
Cut off well below plow depth and restored location.

Name of Plugging Contractor: W & W Production Company License #: 5491
Address: 1150 HWY 39, Chanute, Ks. 66720
Name of Party Responsible for Plugging Fees: Dart Cherokee Basin Operating Co. LLC.
State of Kansas County, Montgomery, ss.
Tony Williams (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 LISA SHARTZTER
Notary Public - State of Kansas
My Appt. Expires 5-26-06

(Signature) Tony Williams
(Address) 211 W. Myrtle, Independence, Ks. 67301

SUBSCRIBED and SWORN TO before me this 24th day of May, 20 06
Lisa Shartzter My Commission Expires: 5-26-06
Notary Public

RECEIVED
MAY 30 2006
KCC WICHITA