

API NUMBER. 15-193-20,442-0000

LEASE NAME Siebert

WELL NUMBER 2

4290 Ft. from S Section Line

3700 Ft. from E Section Line

SEC. 31 TWP. 10S RGE. 31 (E or W)

COUNTY Thomas

Date Well Completed 7-22-87

Plugging Commenced 7-23-87

Plugging Completed 7-23-87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Mid Continent Resources, Inc.

ADDRESS 2805 Bentbay Circle, Wichita, KS 67204

PHONE#(316) 838-9069 OPERATORS LICENSE NO. 8996

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dist. 6 Hays, KS

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size 8-5/8	Put in 322	Pulled out none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped mud to 2544, set 1st plug from 2544' to 2464 w/20 sxs; pumped mud to 1700'; set 2nd plug from 1700' to 1300' w/100sxs; pumped mud to 375' set 3rd plug from 375' to 215' w/40sxs; pumped mud to 40' set solid bridge @ 40' & cement from 40' to surface w/10 sx; pumped 15sx down rathole & 10 sx down mouse hole. All cement 60-40 posmix, 6% gel.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center Bldg. Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center Bldg.

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 87

Carmen L. Adelson

Notary Public

Carmen L. Adelson

My Commission Expires: 8-21-87

7-28-87