

WELL PLUGGING RECORD

Give All Information Completely
• Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Gove County, Sec. 16 Twp. 12 Rge. 30 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NW
Lease Owner Musgrove Petroleum Corporation
Lease Name Wilson Well No. 1
Office Address 407 KEH Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 8 19 52
Application for plugging filed January 8 19 52
Application for plugging approved January 8 19 52
Plugging commenced January 8 19 52
Plugging completed January 8 19 52
Reason for abandonment of well or producing formation Dry

NORTH

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface				8-5/8"	190'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 175 feet.
Set first plug at 175 feet.
Put in 20 sacks cement.
Set second plug at 20 feet.
Put in 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation, Inc.
Address 407 KEH Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
407 KEH Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 19 52.

My commission expires July 9, 1952

Mary Lou Rogers
Notary Public.
01-18-1952



16 14 30 W
137 44

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Wilson #1
 LOCATION: NW NW NW Section 16-12S-30W
 Gove County, Kansas
 COMMENCED: December 19, 1951
 COMPLETED: January 8, 1952

0	5	Cellar
5	178	Surface soil & sands
178	190	Sand, shells, shale
190	1320	Shale
1320	1635	Shale, sand & lime streaks
1635	1870	Shale shells, sand, shale
1870	1980	Shale & shells
1980	2280	Shale & sand, shale & shells
2280	2970	Shale & shells
2970	3060	Shale & shells, lime streaks
3060	3110	Shale
3110	3200	Shale & lime streaks
3200	3269	Shale & shells
3269	3430	Shale & lime streaks
3430	3477	Shale
3477	3655	Shale & lime streaks
3655	3745	Lime & shale
3745	3850	Lime & shale breaks
3850	3990	Lime & shale
3990	4037	Lime
4037	4109	Lime & shale
4109	4154	Lime
4154	4189	Lime & shale breaks
4189	4463	Lime & shale
4463	4515	Dolomite
4515	4545	Lime & shale
4545	4600	Lime
	4600	Rotary Total Depth

Set 190' of 8-5/8" surface casing, cemented with 160 sacks.

Dry and Abandoned.

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Wilson #1, Section 16-12S-30W, Gove County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this fifteenth day of January, 1952.

My Commission expires July 9, 1952.

Shay Len Rogers
 Notary Public

01-18-1952

16 12 30W
 137 48