


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Gove County, Sec. 30 Twp. 12 Rge. 30 W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SW  
Lease Owner George T. Abell  
Lease Name Abell Fee PUB REC Well No. 1  
Office Address Box 430, Midland, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 16 19 51  
Application for plugging filed December 16 19 51  
Application for plugging approved December 16 19 51  
Plugging commenced December 16 19 51  
Plugging completed December 16 19 51  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4645 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface				8-5/8	186'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled w/heavy mud to 4100 feet and from 3950 to 175 feet.  
Set first plug at 4100 feet.  
Put in 25 sacks cement.  
Set second plug at 3950 feet.  
Put in 25 sacks cement.  
Set third plug at 175 feet.  
Put in 1/2 sack hulls and 30 sacks cement.  
Set fourth plug at 40 feet.  
Put in 1/2 sack hulls and 10 sacks cement.

01-05-1952

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 407 KFH Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
407 KFH Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January 1952

Mary Lou Rayer Notary Public.

My commission expires July 9, 1952

PLUGGING  
301 (2) 30W  
328 41

CONTRACTOR'S WELL LOG

COMPANY: George T. Abell  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: Abell #1 Fee  
 LOCATION: SE SE SW Section 30-12S-30W  
 Cove County, Kansas  
 COMMENCED: November 28, 1951  
 COMPLETED: December 16, 1951

0	5	Cellar
5	60	Sand
60	400	Shale
400	700	Gray shale & shells
700	757	Sand
757	1570	Shale, sand & shells
1570	1830	Shale & shells
1830	1945	Shale & lime
1945	2760	Shale & shells
2760	2870	Shale & lime streaks
2870	2950	Shale & shells
2950	3060	Shale & lime streaks
3060	3268	Shale & lime shells
3268	3318	Shale & lime
3318	3385	Shale & lime shells
3385	3855	Shale & lime
3855	4150	Lime
4150	4520	Lime & shale
4520	4595	Lime
4595	4645	Lime & chert
	4645	Rotary Total Depth

Set 186' of 8-5/8" surface casing, cemented with 165 sacks.  
 Dry and Abandoned.

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Abell #1 Fee, Section 30-12S-30W, Cove County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling  
 Secretary-Treasurer

01-03-1952

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this twenty-sixth day of December, 1951.

My Commission expires July 9, 1952.

Mary Lou Lewis  
 Notary Public

**PLUGGING**  
 FILE SEC 30 T 17 R 30W  
 BOOK PAGE 137 LINE 4