

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-5-117

API NUMBER 15-063-21,269-00-00

LEASE NAME Zimmerman

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

3430 Ft. from E Section Line

SEC. 32 TWP. 12 RGE. 20 (N) or (W)

COUNTY Gove

Date Well Completed 6-22-89

Plugging Commenced 6-22-89

Plugging Completed 6-23-89

LEASE OPERATOR National Development Co.

ADDRESS 310 West Central, Suite 117 Wichita, KS 67202

PHONE# (316) 267-1331 OPERATORS LICENSE NO. 5114

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-19-89 (date)

by Dale Baltozor (KCC District Agent's Name).

to be filed by \_\_\_\_\_  
 Is ACO-1 filed? operator If not, Is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4017'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 2370' w/25 sacks 60/40 pozmix 6% gel thru drill pipe  
 Next Plug: @ 1388' w/100 " " " " " " " " 15 sacks in Rat Hole  
 Next Plug: @ 250' w/40 " " " " " " " " 10 sacks in Mouse Hole  
 Top Plug: @ 40' w/10 sacks " " " " " " " " 10 sacks in Mouse Hole  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lobo Drilling Co. 06-29-1989


STATE OF Kansas COUNTY OF Barton, ss. Wichita, Kansas

Ervin Neighbors (Employee of Operator) ~~XXXXXXXXXXXXXXXXXXXX~~  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors  
 (Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 28 day of June, 1989

Dorothy M. Hague  
 Notary Public



My Commission Expires: 5-5-90

15-063-21269-00-00

DRILLER'S WELL LOG

DATE COMMENCED: June 17, 1989  
DATE COMPLETED: June 22, 1989

National Development  
ZIMMERMAN #1  
130' W of C N/2 NE SW  
Sec. 32, T12S, R30W  
Gove County, Ks.

0 - 231' Surface Soil, Shale, Sand  
231 - 2401' Shale  
2401 - 3498' Lime & Shale  
3498 - 3655' Lime  
3655 - 4005' Lime & Shale  
4005 - 4017' Lime  
4017' RTD

ELEVATION: 2871 K.B.

SURFACE PIPE: Set new  
8-5/8", 20# pipe @229'  
w/145 sacks 60/40 pozmix  
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and  
statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*

Subscribed and sworn to before me this 28 day of June 1989.



*Dorothy M. Hague*  
Notary Public

STATE OF KANSAS  
STATE OF KANSAS  
AUG 31 1989  
08-31-1989  
Wichita, Kansas

15-063-21269-00-00

DRILLER'S WELL LOG

DATE COMMENCED: June 17, 1989  
DATE COMPLETED: June 22, 1989

National Development  
ZIMMERMAN #1  
130' W of C N/2 NE SW  
Sec. 32, T12S, R30W  
Gove County, Ks.

0 - 231' Surface Soil, Shale, Sand  
231 - 2401' Shale  
2401 - 3498' Lime & Shale  
3498 - 3655' Lime  
3655 - 4005' Lime & Shale  
4005 - 4017' Lime  
4017' RTD

ELEVATION: 2871 K.B.

SURFACE PIPE: Set new  
8-5/8", 20# pipe @229'  
w/145 sacks 60/40 portmix  
2% gal 3% cc.

AFFIDAVIT

STATE OF KANSAS  
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

JUN 29 1989

CONSERVATION DIVISION  
Wichita, Kansas  
*Ervin Neighbors*

Subscribed and sworn to before me this 28 day of June 1989.

*Dorothy M. Hague*  
Notary Public

