

11-29

6 2319

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,285-000d

SE SE SW, SEC. 24, T. 10 S, R 31 W/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Robben Well # 1

Operator: Ritchie Exploration Inc.

County Thomas 149.34

Name & Address 125 N. Market Suite 1000

Well Total Depth 4595' feet

Wichita, Ks. 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 328

RECEIVED STATE CORPORATION COMMISSION

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso, Kansas License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 28 Month: Nov Year: 19 88

Plugging proposal received from Duntz

(company name) Kelso (phone) _____

were: 8 5/8" set at 328' w/240 sks. 4 1/2" set at 4593' w/225 sks. Perfs 4038' -4436'.

Order sand and Common Cement. Pull pipe. Order 200 sks 65/35 Poz 10% Gel 2% Dical 500#

Hulls. Allied Cement Co. Hensley Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45PM Day: 28 Month: Nov Year: 1988

ACTUAL PLUGGING REPORT Sand bottom to 3980' w/4 sks Common Cement on sand w/bailer.

Recovered 1500' of casing w/shots at 2400' - 2200' - 1800' - 1600'. Squeezed 8 5/8"

w/200 sks cement and 500# Hulls to max psi 1000#. Close in psi 1000#. Plug complete.

Wireline ran to anhydrite.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INVOICED DATE 1-25-89

Handwritten signature