

6 031407

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-193-20279-0000
SE SW SE, SEC. 25, T 10 S, R 31 W/E XXX

TECHNICIAN'S PLUGGING REPORT

Operator License # 07506

Operator: First Energy Corp
Name & Address 16701 Greenspoint Park Drive
Houston, Texas 77060

330 feet from S section line
1650 feet from E section line

Lease Name Summers Well # 68-25

County Thomas 149.82

Well Total Depth 4610 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Oakley, Ks.

Company to plug at: Hour: PM Day: 28 Month: August Year: 19 90

Plugging proposal received from Earl Eavers Bill Dean

(company name) First Energy Corp (phone) _____

were: 8 5/8 set at 319 w/225 sks. 4 1/2 set at 4609 w/325 sks. PBD 4185.

Perf lancing H zone 4116 - 22. Port collar 2463 cwc w/500 sks. Order 225 sks 65/35 poz

8% gel 500 lbs. hulls. B. J. Titan Cement Co. Hensley Water Truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45PM Day: 28 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sq 4 1/2 casing w/225 sks cement blend w/500 lbs

hulls mixed into max psi 100 lbs. Close in psi 900 lbs. Plug complete.

STATE CORPORATION COMMISSION
SEP 10 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE: 9-17-90
INV. NO. 29331

Phil G.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow