

8-24

212  
2

4- 031738

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-063-20,400-00-00

C NE NE /4 SEC. 04 , 12 S , 30 W  
4620 feet from S section line  
660 feet from E section line

Operator license# 5701

Lease Jensen well # 1-A

Operator: National Oil Company

County Gove

Address: P.O. Box 399  
Garden City, Kansas 67648

Well total depth 4468 feet <sup>145.26</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 247 feet

Aband. oil well  , Gas well  , Input well  , SWD  , D & A

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 24 Month: August Year: 92

Plugging proposal received from: Dean Ives

Company: National Oil Company Phone: \_\_\_\_\_

Were: Order 350 sx. 60/40 pozmix - 10% gel. - 500# hulls.  
Hole open by wireline.  
Shots @ 1960' and 1150'.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:45P.M. , Day: 24 , Month: August , Year: 92

Actual plugging report: 8 5/8" set @ 247' w/175 sx. cwc. 4 1/2" set @  
4465' w/125 sx. O.H. 4465' - 4468'. Ran tubing to 1940' spotted 50 sx.  
cement blend. Laid down tubing to 1170' circulated cement to surface.  
Laid down tubing. Squeezed 4 1/2" with total 125 sx. cement blend w/400  
sx. hulls mixed in to Max. P.S.I. 800#. Close in P.S.I. 300#.  
Squeezed 8 5/8" w/140 sx. cement blend w/100# hulls mixed in to Max.  
P.S.I. 300#. Close in P.S.I. 200#. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING  , CASING  . Elevation: \_\_\_\_\_

I did[  ] / did not[  ] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

10-8-92  
36394

HO

RECEIVED  
STATE CORPORATION COMMISSION  
09-16-1992  
SEP 16 1992  
CONSERVATION DIVISION  
Wichita, Kansas