

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-063-20, 626 00 00

SE, Sec. 4, T 12 S, R 30 W

330 feet from N/E section line

1250 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6077

Lease Name Vollbracht Well # 1

Operator: T. Childreiff Oil & Exploration
Name &
Address Rt 2, Box 214, Rogersville, Mo. 65742

County Grove

Well Total Depth 4503 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 121'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 602

Address Rt 2, Box 214, Rogersville, Mo. 65742

Company to plug at: Hour: 8:30 PM Day: 5 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Keith Vanpelt

(company name) Murfin Drilling Co. (phone) 316-267-3241

were: Order 180 sacks 50 pos mix - 6% Gel. - 3% Cal. Cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 2295' w/ 20 sacks. 2nd plug C 1450' w/ 100 sacks. 3rd plug C 175' w/ 40 sacks. 4th plug - solid bridge of hulls & plug C 40' w/ 10 sacks. Circulate 10 sacks in rat hole.

No Arbachle

Signed Keith Vanpelt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 PM Day: 5 Month: 11 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 121' - SR. case w/ 125 sacks 50 pos mix - 3% Cal. Cl.

Ordered 180 sacks 50 pos mix - 6% Gel. - 3% Cal. Cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 2295' w/ 20 sacks. 2nd plug C 1450' w/ 100 sacks. 3rd plug C 175' w/ 40 sacks. 4th plug - solid bridge of hulls & plug C 40' w/ 10 sacks. Circulated 10 sacks in rat hole.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1982
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I ~~was~~ / did not) observe this plugging.

INVOICED
DATE 12-27-82
INV. NO. 2008-W

Signed Keith Vanpelt
(TECHNICIAN)