

6 070907

310

1762

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,379-00-00  
SE NE SW, SEC. 10, T 12 S, R 30 W/E<sup>xx</sup>

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

1650 feet from S section line

2970 feet from E section line

Operator: Pickrell Drilling Co Inc  
Name & Address: 110 N Market #205  
Wichita, Ks. 67202  
DON Beanchamp

Lease Name Zimmerman Well # 0 #1

County Gove 144.20

Well Total Depth 4437 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A <sup>x</sup>

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pickrell Drilling Co. License Number \_\_\_\_\_

Address Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 10 Month: Mar Year: 19 91

Plugging proposal received from Doyle Folkers

(company name) Pickrell Drilling Co. (phone) \_\_\_\_\_

were: 8 5/8 271 ft. s.p. cwc w/160 sks 60/40 poz 2% gel 3% cc. By Allied.

Miss well. Elv. 2795 anhy 2264. Mud condition 45 vis. 9.4 lbs. 10 w.l.

Proposal 200 sks 60/40 poz 6% gel 3% cc. Circ hole 42 - 45 vis. Spot and displace  
cement through drill stem, heavy mud between all plugs. 25 sks at 2275;

100 sks w/1 sk f.c. at 1390 ft; 50 sks at 320 ft; 10 sks at 40 ft.; 15 sks rathole.  
Circulated.

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None <sup>x</sup>

Operations Completed: Hour: 11:00PM Day: 10th Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Pickrell ordered 200 sks 60/40 poz 6% gel 3% cc. Circulated hole;

Spotted and displaced cement through drill stem, heavy mud between all plugs.

1st plug at 2275 w/25 sks cement 4th plug at 40 ft. w/10 sks cement

2nd plug at 1390 w/100 sks cement w/1 sk f.c. 15 sks rathole (cir)

3rd plug at 320 w/50 sks cement.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

INVOICED (did/did not) observe this plugging.

DATE 4-22-91  
INV. NO. 31285

G.S.

Signed Marion J. Schmidt  
(TECHNICIAN)