

To: 1 090173
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-11 15-033-20847-00-09 22
API NUMBER 15- 033-20,847

NE SE SW, SEC. 34, T. 34 S, R. 20 W/E

1150 feet from S section line

2475 feet from ^W X section line

Lease Name Miller Well # 5-34

County Comanche 212.22

Well Total Depth 6530 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 670

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145

Operator: Roberts & Murphy, Inc.

Name & Address P.O. Box 7125

Shreveport, LA 71107

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Triad Drilling Co. License Number 7345

Address 5400 N. Grand Blvd., Suite 310, Oklahoma City, OK 73112

Company to plug at: Hour: 5 p.m. Day: 11 Month: 3 Year: 19 92

Plugging proposal received from Lloyd Hubbard

(company name) Triad Drilling Co. (phone) 405-948-6006

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 850'

1st plug at 850' with 50 sx cement, 2nd plug at 680' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

_____ Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 p.m. Day: 11 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement,

2nd plug at 680' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1992
3-17-1992
CONSERVATION

Remarks: Used 60/40 Pozmix 6% gel by Western.
(If additional description is necessary, use BACK of this form.)

I ~~did~~ / did not) observe this plugging.

4-7-92
34893

Signed _____
(TECHNICIAN)